

Woorinen Pipeline Project – Stages 2 & 3, Vic

- Client Goulburn Murray Rural Water Authority
- Year Constructed 2003

The scope of work included the construction of 80km of pipelines ranging in size from 225mm diameter PVC to 1,050mm diameter Hobas pipes. The principal items of work included the clearing, grading, laying, jointing and backfilling of pressure pipelines through road reserves as well as some 30km of “on farm” works involving the construction of air valves, scour valves, associated fittings and anchor blocks.

The success of the project through a heavily irrigated stone fruit district was as a direct consequence of close liaison with each farm holder. Construction requirements included the diversion and maintenance of existing concrete / clay line channels while the pressure pipeline was constructed.

